



भारतीय भूमि पत्तन प्राधिकरण
गृह मंत्रालय, भारत सरकार
Land Ports Authority of India
Ministry of Home Affairs Government of India

कार्यकारी अभियंता
भारतीय भूमि पत्तन प्राधिकरण, लोक नायक
भवन, खान मार्केट, नई दिल्ली-110003
फोन नंबर:- 011-24340782
ईमेल:- exen-civil21@lpai.gov.in

Executive Engineer
Land Ports Authority of India, Lok Nayak
Bhawan, Khan Marker, New Delhi-110003
Phone No:- 011-24340782
Email:- exen-civil21@lpai.gov.in

N-11016/49/2026/FencingWork/Panitanki

Dated: 22nd April, 2026

NOTICE INVITING QUOTATION

The Executive Engineer, Land Ports Authority of India (LPAI), Ministry of Home Affairs, Govt. of India, 1st Floor, Lok Nayak Bhawan, Khan Market, New Delhi - 110003 on behalf of the Chairman, LPAI, invites offline percentage rates Quotations from eligible Contractors for execution of the work as per below detail: on the same day at 03:30 PM,

S.No.	Description	Details
1	Name of Work & Location	Fencing work of Land parcel adjacent to Mechi River at ICP Panitanki.
2	Estimated Cost	Rs.24,10,972.00
3	Quotation Submission Start Date	From 15:00 Hrs. on 22/04/2026.
4	Quotation Submission End Date	Upto 15:00 Hrs. on 28/04/2026.
5	Opening of Quotations	15:30 Hrs. on 28/04/2026, in the presence of the Quotationers or their authorized representatives, if they wish to be present.
6	Performance Bank Guarantee	5% of the Work Order Amount
7	Security Deposit	2.5% of the Work Done Amount
8	Period of Completion	45 Days
9	Defect Liability Period	180 Days

2. Contractors who fulfil the following requirements shall be eligible to apply:

Should have satisfactorily completed the works as mentioned below during the last Seven years ending last day of the month previous to the one in which Quotations are invited.

Three similar works each costing not less than Rs.9.65 Lakh
or
Two similar works each costing not less than Rs.14.47 Lakh
or
One similar work costing not less than Rs.19.29 Lakh

Similar work shall mean works of Boundary Wall / Fencing Work. The value of executed works shall be brought to current costing level by enhancing the actual value of work at simple rate of 7% per annum; calculated from the date of completion to previous day of last date of submission of Quotations.

3. All contractors shall be required to submit the following documents along with the Application, duly signed, stamped, and dated, **failing which their applications shall not be considered.**

- (i) Copy of GST Registration Certificate.
- (ii) Copy of Pan Card.
- (iii) Copy of MSME Certificate.
- (iv) Similar Work Completion Certificates.

4.

Terms & Conditions:

- (i) The work shall be executed in accordance with CPWD Specifications along with the latest correction slips and as per the directions of the Engineer-in-Charge.
- (ii) The quoted rates shall be inclusive of all applicable taxes, and no extra payment shall be made on any account whatsoever.
- (iii) The undersigned reserves the right to cancel or terminate the work order at any time without assigning any reason whatsoever.
- (iv) The L-1 Quotationer shall be required to submit a Performance Bank Guarantee equivalent to 5% of the Work Order amount.
- (v) Any damage caused to the premises during execution of the work shall be made good by the contractor at his own cost, and no extra payment shall be admissible on this account.
- (vi) Necessary statutory deductions such as Income Tax, GST, etc. shall be made as per applicable rules.
- (vii) Security Deposit @ 2.5% shall be deducted from the gross amount of work done and shall be released after completion of 6 month DLP period.


Nirmal Singh Bhati
Executive Engineer (Civil)
Phone No: - 011-24340782
Email: exen-civil21@lpai.gov.in

Copy to:

LPAI HQ Notice Board

COST ESTIMATE FOR FENCING WORK AT PANITANKI						
S.No.	DSR 2023	Description of Item	Unit	Rate	Quantity	Amount
1	16.18	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used.				
	16.18.1	With G.I. barbed wire	Metre	22.10	10500.00	₹ 2,32,050.00
2	16.19	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete.	Kg	125.75	7650.00	₹ 9,61,987.50
3	4.20	Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/ Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the minimum specified cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	4.20.1	All works upto plinth level				
	4.20.1.2	Concrete of M15 grade with minimum cement content of 240 kg /cum	Cum	8986.15	82.62	₹ 7,42,435.71
4	2.30	Excavating holes more than 0.10 cum & upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc, disposing of surplus excavated soil, as directed within a lead of 50 m and lift upto 1.5 m.				
	2.30.1	All kinds of soil.	Each	82.45	680.00	₹ 56,066.00
TOTAL						₹ 19,92,539.21
COST INDEX @ 21% (Adopted from Siliguri District)						₹ 4,18,433.23
GRAND TOTAL						₹ 24,10,972.45
SAY						₹ 24,10,972.00

[Handwritten signature]

[Handwritten signature]

